



ADDENDUM #1
ITB/RFP NUMBER: 2022018-PW-B
Annual Street Paving Services ITB

DATE: February 16, 2022

TO: All Potential Bidders/Offerors

City of Harrisonburg's ITB, is modified as follows:

On February 11, 2022 at 2:00pm local time a mandatory pre-bid meeting was held for the above-referenced solicitation. Attached and made part of this addendum is the sign-in sheet from this meeting as well as highlights, clarifications and questions and answers from the pre-bid meeting.

Bidders should take note of the modified bidding dates listed herein.

All other requirements, terms and conditions of the ITB/RFP remain unchanged.

Addendum page must be signed and returned with your bid/proposal to acknowledge receipt of this addendum.

Authorized Signature

By: Shane B. Smith
Procurement Manager

PRE-BID ATTENDANCE
Annual Paving Services
Feb. 11, 2022

NAME (Please Print)	COMPANY	PHONE	EMAIL
Frank Breeden	PavCon	540-908-9592	Frank.Breeden@conmatgroup.com
Gregg Shultz	Adams Constr. Co.	540-434-3878	gshultz@adamspaving.com
Andy Powell Aaron Rhoney Danielle Morris Jason Ward BJ Crawford	City of Harrisonburg	540-434-5928	Andy.Powell@harrisonburgva.gov Aaron.Rhoney@harrisonburgva.gov Danielle.Morris@harrisonburgva.gov Jason.Ward@harrisonburgva.gov BJ.Crawford@harrisonburgva.gov

PRE-BID CONFERENCE MEETING MINUTES

PROJECT: ANNUAL STREET PAVING SERVICES # 2022018-PW-B

DATE: FEB. 11, 2022

TIME: 2:00 PM

LOCATION: GOTO MEETING

AGENDA ITEMS

1. Introductions

2. Anticipated Schedule

- Written questions due **Feb. 23, 2022** at 12:00pm (received via Purchasing Dept.)
Questions@harrisonburgva.gov
- Receive and open bids – **March 4, 2022** at 3:00pm (bids due in Purchasing on 3rd Floor – to be opened in room #11 at City Hall)

3. Project Overview

- Description of project
- Existing conditions

4. Bid Documentation and Paperwork

- Please make sure all forms are filled out completely. List of what is required is in Section 0100 #2, D

5. Questions

Is there a street list for the paving schedule? It will be included with the first addendum.

Is there a rebuild list for the manholes and water valves? We are working on the list and it will be made available soon.

There are two completion dates. Which one is correct? November 15, 2022 is the correct date.

Phase 1 Completed by 8/12/2022		WIDTH	LENGTH	SY	MILES	MIX	LBS. SY	TONS
MT. CLINTON PIKE	N.Liberty - R.R.	44	2155	10536	0.41	12.5D	235	1238
	R.R. - Virginia	36	200	800	0.04	12.5D	235	94
GARBERS CHURCH RD	W.Market - Heritage ent.	44	3515	17185	0.67	12.5D	235	2019
GAY ST	Virginia - Chicago	39	550	2,385	0.10	12.5D	235	280
PEACH GROVE AVE	Port - Stonespring	36	3115	12,460	0.59	12.5D	235	1470
NEFF AVE	Reservoir - Valley Mall	36	2675	10,700	0.51	12.5D	235	1260
KEEZLETOWN RD	Country Club - E.C.L	27	4066	12,198	0.77	12.5D	235	1435
				66,264				7796

Phase 2 Completed by 11/11/2022		WIDTH	LENGTH	SY	MILES	MIX	LBS. SY	TONS
WOLFE ST	Liberty - Chicago	38	1050	4433	0.20	9.5AL	165	366
	Chicago - Brook	38'	211'	891	0.17	9.5AL	165	80
	Brook - Willow	30'	581'	1937	0.37	9.5AL	165	165
WASHINGTON ST	N.Main - N.Liberty	24	1280	3413	0.24	12.5D	235	401
JEFFERSON ST	Washington - Ashby	27	1056	3168	0.20	9.5AL	165	261
EARLY RD	Pleasant Valley - S.C.L.	28	5702	17740	1.08	12.5D	235	2084
Le RAY CIR	Early - Cul de Sac	36	1100	5272	0.21	9.5AL	165	443
OTT ST	Franklin - Paul	35	1485	5775	0.28	9.5AL	165	476
ROCKBRIDGE CIR	South - Cul de Sac	28	375	1725	0.07	9.5AL	165	146
SOUTH AVE	High - D.E.	37	1267	5209	0.24	12.5D	235	612
	S.Main - High	31 - 36	2675	10,142	0.51	12.5D	235	1192
MANOR DR	Stonespring - Cul de Sac	30	765	2550	0.14	9.5AL	165	220
KRAMER ST	Gilmer Cir. - Cul de Sac	30	475	1585	0.09	9.5AL	165	140
WATERMAN DR	Taliaferro - Cul de Sac	30	435	1450	0.08	9.5AL	165	185
CLARA CT	Stonechris - Cul de sac	30	585	1950	0.37	9.5AL	165	226
BROOKSIDE CT	Shenstone - Cul de Sac	30	225	750	0.14	9.5AL	165	127
HARMONY DR	Virginia - E.O.P.	31	1850	6372	1.21	9.5AL	165	525
IVY LN	College - Cul de Sac	30	300	1000	0.19	9.5AL	165	133
				75,362				3493
								4289