



ADDENDUM #1
ITB/RFP NUMBER: 2022020-PW-B
Bridge Rehabilitation ITB

DATE: March 24, 2022

TO: All Potential Bidders/Offerors

City of Harrisonburg's ITB, is modified as follows:

On March 23, 2022 at 2:00pm local time a mandatory pre-bid meeting was held for the above-referenced solicitation. Attached and made part of this addendum is the sign-in sheet from this meeting as well as highlights, clarifications and questions and answers from the pre-bid meeting.

All other requirements, terms and conditions of the ITB/RFP remain unchanged.

Addendum page must be signed and returned with your bid/proposal to acknowledge receipt of this addendum.

Authorized Signature

By: Shane B. Smith
Procurement Manager

**PRE-BID ATTENDANCE
BRIDGE REHABILITATION
MARCH 23, 2022**

NAME (Please Print)	COMPANY	PHONE	EMAIL
Jacob Truxell	Fairfield Echols	540-337-1201	JTruxell@fairfieldechols.com
Daniel Runion	Burleigh Construction	434-993-2214	drunion@burleighconstruction.com
Aaron Rhoney Danielle Morris Andy Powell Jason Ward Doug Adams	City of Harrisonburg	540-434-5928	Aaron.Rhoney@harrisonburgva.gov Danielle.Morris@harrisonburgva.gov Andy.Powell@harrisonburgva.gov Jason.Ward@harrisonburgva.gov Doug.Adams@harrisonburgva.gov
Kaila Stevens Chad Thomas	Mattern & Craig	540-345-9342	kesteven@matternandcraig.com cmthomas@matternandcraig.com

HARRISONBURG BRIDGE REPAIRS
CITY OF HARRISONBURG, VIRGINIA
ITB NO. 2022020-PW-B

M&C COMM. NO. 4192A
PRE-BID CONFERENCE
March 23, 2022 @ 2:00 PM

1. Sealed bids for the Harrisonburg Bridge Repairs will be received by the City of Harrisonburg by mail or in person at the City of Harrisonburg Purchasing Office located in City Hall at 409 South Main Street, Third Floor, Harrisonburg, VA until 3:00 p.m., Thursday, April 7th, 2022 and then publicly opened and read aloud.
2. All questions and requests for information shall be submitted in writing to the City of Harrisonburg Purchasing Office and shall be addressed to Shane Smith (questions@harrisonburgva.gov) by 12:00 PM on March 31, 2022. All responses will be in writing and will be posted as an addenda at www.harrisonburgva.gov/bids-proposals. It is the responsibility of all Bidders to ensure that they have received all addenda and to include signed copies of any and all addenda with their bid submission
3. The work is located on the in the city limits of Harrisonburg. The following is a brief summary of the work.
 - a. Bridge No. 1804 – US Route 11 Southbound (S Liberty Street) over Blacks Run
 - Repair epoxy overlay
 - Concrete (Class A4) for sidewalk
 - Replace joint sealant
 - b. Bridge No. 1805 US Route 11 Southbound (N Liberty Street) over Blacks Run
 - Epoxy overlay – sidewalks and median
 - Concrete (Class A4) for sidewalk
 - Replace joint sealant
 - c. Bridge No. 8006 – West Rock Street over Blacks Run
 - Seal cracks in deck and sidewalks
 - Replace joint sealant
 - d. Bridge No 8020 – State Route 280 (Stone Spring Road) over NS Railway and Blacks Run
 - Fixed bearing work
 - Expansion bearing work
 - Epoxy overlay – sidewalks and median
 - Waterproofing – parapets
 - Seal cracks in deck and sidewalks

4. Contract time shall be fixed completed with a date of November 30, 2022. The project is a unit price project and payment applications will be processed monthly. Liquidated damages for this project will be applied as specified in the 2016 VDOT Road and Bridge Specifications Section 108.06.b.
5. Various items on this project require shop drawing submittal by the Contractor for approval by the Engineer. Those items include, but are not limited to, the following: repair materials, and bearing work details.
6. All construction and materials will conform to the project documents and plans.
7. Specific items of the work are highlighted below:
 - a. Descriptions of all pay items can be found in the VDOT Road and Bridge Specifications, 2016 or as modified/clarified in the Project Manual, Sections 1A, 2A, 3A, and Special Provisions.
 - b. This portions of the roadways will be closed during construction The Contractor is responsible for providing traffic control services on the structures in accordance with the State and Federal “Manual for Uniform Traffic Control Devices” and the “VDOT Work Area Protection Manual.”

Meeting Minutes:

1. City construction inspection staff will be on site and will work with contractors during MOT and if other issues arise.
2. There is a potential overlap of MOT with a different city bridge project downtown. City will advise if this becomes an issue.
3. Best time to do the work is during the summer when the college students are gone.
 - a. Summer break is between second week of May and second week of August.
4. Error found on drawing sheet B-5. In plan view, number 3 and 5 shall be switched to point to the correct corresponding area of work.